

# Engineer Estimate of Construction Costs



**Title:** Hallows Hotel - Lift Station Upgrades

**Date of Estimate:** October 4, 2018

**Owner:** City of Ingleside

**Hanson Engineer:** Craig Thompson, P.E.

**Contact:**

**Hanson Contact:**

**Address:**

4501 Gollihar Road  
Corpus Christi, Texas 78411

**Phone:**

**Phone:** (361) 814 - 9900

## LIFT STATION UPGRADES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	CONTRACT UNIT PRICE	TOTAL COST
1	SWPPP Construcion and Maintenance	1	EA	\$2,500.00	\$2,500.00
2	Access Roadway - 8" Crushed Limestone	3,500	SF	\$2.50	\$8,750.00
3	Additional Wet Well - 6' Diameter	1	EA	\$7,500.00	\$7,500.00
4	Concrete Cap - 8" Reinf. Concrete	150	SF	\$15.00	\$2,250.00
5	Yard Piping / Connect Proposed Wetwell	1	LS	\$2,500.00	\$2,500.00
6	Headworks and Valves	1	LS	\$5,000.00	\$5,000.00
7	4" Forcemain	1,800	EA	\$30.00	\$54,000.00
8	Connect FM to existing Sanitary Manhole	1	EA	\$2,500.00	\$2,500.00
9	Lift Station Controls and Electrical Upgrades	1	LS	\$7,500.00	\$7,500.00
10	Pump Upgrades	2	EA	\$7,500.00	\$15,000.00
<b>Construction Costs:</b>					<b>\$107,500.00</b>
<b>20% Contingency Costs</b>					<b>\$21,500.00</b>
<b>Total Expected Construcion Costs</b>					<b>\$129,000.00</b>